

Terms & Conditions Issued by:

Warehouse Floor Marking Ltd, (referred to as 'Warehouse Floor Marking' and 'WFM')

79 Overlea Drive, Hawarden, Flintshire, CH93HR

All internal areas will take in the region of 24 hours to fully cure at an ambient temperature (no less than 10 degrees Celsius) if this temperature can't be achieved, please raise this with your WFM project manager as it may affect curing times.

Warehouse Floor Marking Ltd cannot guarantee or offer any guide of life expectancy for internal line markings that are laid onto an unprepared surface. If durable lines are needed or in areas that receive MHE traffic, we strongly advise that the concrete is shot blasted prior to painting.

The quotation assumes that the floor will be cleaned by the client prior to the lines being installed unless otherwise stated in the quotation.

Our quotation is based on 10 hours of unhindered access per day, any delays to installation caused by access / site issues, will be charged at a pro rata rate.

If a power supply is being provided by the client to power our floor preparation equipment, the supply needed is a 3 phase, 16 amp, 110v, 5 pin point within 50m of all working areas. If this is not available, a generator will need to be hired at an extra cost. Any delays caused by a faulty power supply that has been provided by the client will be charged at a pro rata rate.

Warehouse Floor Marking Ltd will provide a layout of the line markings to be installed for your approval prior to installation commencing, any changes to this layout must be communicated to the project manager and not agreed at site level with the installation team.

We request that a nominated representative from your organization with knowledge of the project be on site on the first day of installation to receive our team and also be contactable for the duration of our visit. We also request that the nominated

person be available at the end of the installation to complete a project sign of sheet to confirm you are satisfied with the installation.

It is the responsibility of the client to provide sufficient lighting in the work areas for the duration of the installation and to provide the use of MHE to unload materials.

Empty paint cans and consumables associated with the installation that are not hazardous will be disposed of in the clients skip, if this is not permitted, please make your WFM project manager aware as a skip may need to be hired at an extra cost.

Shot blasted floor preparation gives the edge of painted lines a 'feathered' effect, this is a sign of durability and should not be confused with 'bleed' on the markings.

Any quotation given by us is based on the installation of paint to a micron thickness equivalent to that of two coats, due to the chemical bonding properties of the paint, it is not always necessary to paint two separate coats. The equivalent amount of paint can usually be installed in one coat.

Should the type of concrete or painting surface be more porous than usual, it may be required that we use more paint to complete the installation. This is something we are not able to value until the installation has begun. We will make every effort to reduce the impact to you however any charges for additional paint which is required which were not foreseen upon the quotation will be charged to you.